



PROJECT TITLE

P881 Platform & Pipe Laying Installation.

DATE

February/March 2011.

BACKGROUND

KTL Offshore supplied the heavy lift slings and grommets which were used for the installation of 11 offshore platforms and 16 subsea pipelines spanning 70 km in the Gulf of Thailand.

ITEMS

- 16 KimFlex Slings, 128mm dia x 14m length, MBL 581 MT.
- 6 KimFlex Slings, 160mm dia x 46.50m length, MBL 892 MT.
- 4 KimFlex Slings, 256mm dia x 19.50m length, MBL 2167 MT.
- 4 KimFlex Slings, 220mm dia x 19.50m length, MBL 1778 MT.
- 4 KimFlex Slings, 192mm dia x 19.90m length, MBL 1253 MT.

P881 PLATFORM & PIPE LAYING INSTALLATION (Thailand)

KimFlex Slings, Cable Laid Grommets and Crosby Shackles



- 4 KimFlex Slings, 184mm dia x 40.70m length, MBL 1166 MT.
- 4 KimFlex Slings, 184mm dia x 38m length, MBL 1166 MT.
- 4 KimFlex Slings, 176mm dia x 19.90m length, MBL 1094 MT.
- 2 KimFlex Slings, 160mm dia x 51.10m length, MBL 892 MT.
- 2 KimFlex Slings, 160mm dia x 14m length, MBL 892 MT.
- 2 Cable Laid Grommets, 120mm dia x 4m length, CGBL 1265 MT.

All manufactured and tested by KTL Offshore in Singapore. Witnessed and certified by ABS 3rd party consultancy.



- 18 G-2160 Crosby Wide Body Shackles, 300 MT.
- 12 G-2160 Crosby Wide Body Shackles, 400 MT.
- 4 G-2160 Crosby Wide Body Shackles, 500 MT.
- 4 G-2160 Crosby Wide Body Shackles, 600 MT.